

IT 认证电子书



质 量 更 高 服 务 更 好

半年免费升级服务

<http://www.itrenzheng.com>

Exam : NS0-192

**Title : NetApp Certified Support
Engineer**

Version : DEMO

1.A customer recently performed an ONTAP upgrade and would like to confirm the successful completion of the process.

Which three actions would satisfy this requirement? (Choose three.)

- A. Execute the version command at the cluster shell.
- B. Verify the version from the new AutoSupport that was automatically triggered after an upgrade.
- C. A System Message notification will be shown upon reboot after a successful upgrade.
- D. Execute the system node upgrade-revert show command at the cluster shell.
- E. Execute the system node upgrade-revert show-task-status command at the cluster shell.

Answer: A,C,D

2.You are adding an additional node to a single-node cluster.

Which of the actions should be performed after this upgrade? (Choose two.)

- A. Verify that HA is enabled.
- B. Verify that epsilon is not assigned.
- C. Verify that epsilon is assigned.
- D. Verify that HA is disabled.

Answer: C,D

3.Using QoS statistics for a group of volumes on one node, you notice that most of the latency comes from the data layer.

In this scenario, which statement is correct?

- A. There is too much indirect traffic from other nodes.
- B. QoS processing is increasing CPU usage.
- C. The CPU on the node is overused.
- D. High disk use is increasing CPU usage.

Answer: D

4.A manager wants a volume to have a guaranteed 300 MB/s of read performance. You explain that you cannot do this on FAS storage running ONTAP 9.3 backed by 10,000 RPM disks.

What is the reason for this response?

- A. Throughput floors apply to only iSCSI access.
- B. Throughput floors can only guarantee up to 125 MB/s.
- C. Throughput floors require a license.
- D. Throughput floors require AFF.

Answer: D

5.Click the Exhibit button.

Workload	ID	Latency	Network	Cluster	Data	Disk	QoS	NVRAM
ms_sql_backup..	1234	4.59ms	62.00us	0ms	4.53ms	0ms	0ms	0ms
ms_sql_backup..	1234	120.22ms	55.00us	0ms	153.00us	0ms	119.99ms	0ms
ms_sql_backup..	1234	99.45ms	88.00us	0ms	186.00us	0ms	99.23ms	0ms
ms_sql_backup..	1234	106.78ms	54.00us	0ms	183.00us	0ms	106.51ms	0ms

A backup administrator notices throughput problems during backup jobs. While the job is running, you review the QoS output for the target volume.

Referring to the exhibit, which statement is correct?

- A. The volume is encountering the QoS limit.
- B. The network is slow.
- C. The data layer of the controller is slow.
- D. The traffic is going over an indirect path in the cluster.

Answer: A